
## William N. Lamarre Concrete Products, Inc. "L" FLO-DUC DISSIPATOR

## HD Top loading Only

Drawing Not to Scale



- Notes
- Concrete strength f'c 4000PSI@28 days. Density 150 PCF.
- 2. Cement, Portland Type II or III, ASTM C150-81
- 3. Admixtures, air & plasticizers per ASTM C233-82
- 4. Reinforcement per ASTM C1227-latest revision
- 5. Conforms to Mass Title V specifications
- 6. 6 3/8" Slots in Flo Duct 2 located 2' in from each side & 2 in center